

CARE & MAINTENANCE

Oliveri uses the highest sanitary grade acrylic, however naked flames, cigarettes or strong chemicals will damage the bath and must be avoided and/or removed immediately. To preserve the high gloss acrylic surface, note the following:

When filling the bath, start with cold water to allow the bath to gradually adapt to the changing temperature. After using your bath, clean with a soft cloth and warm soapy water to clean away any oils or soap, to prevent tide marks and preserve the high-gloss surface. Clean using warm soapy water and only mild liquid detergents. Do not use powders, pastes, creams, chemicals, window cleaning sprays or abrasive cleaners.

Any scratches that do occur can be removed with a fine polish like Brasso.

WARRANTY

We provide the following warranty for products purchased in Australia or New Zealand from authorised Oliveri resellers for use in domestic residential (indoor) or commercial (indoor) installations (Products). Commercial installations include all non-residential installations including hotels, motels, gyms, clubs, factories, schools, hospitals, restaurants and aged care facilities. This warranty is in addition to our responsibility to customers under all other statutory and regulatory requirements. The applicable warranty period set out below (Warranty Period) starts at the original date of purchase.

PRODUCT	COMPONENT	DOMESTIC USE	COMMERCIAL USE
Baths Freestanding	Bath Shell	10 year replacement parts, 1 year labour	7 year replacement parts, 1 labour labour
	Adjustable Feet	1 year replacement parts & labour	1 year replacement parts & labour
	Waste & Overflow	1 year replacement parts & labour	1 year replacement parts & labour

WARRANTY STATEMENT

- (a) Our Products come with guarantees that cannot be excluded under the Australian and New Zealand consumer law. You are entitled to a replacement or refund for a major failure and for compensation for any other reasonably foreseeable loss or damage.
- (b) If during the applicable Warranty Period, a Product has a material defect which arose in the course of manufacture then, subject to the warranty conditions below being met, you may submit a warranty claim to us by email or calling our Customer Care Centre:

**Australia**  
Ph: 08 8348 6444 (select Service & Warranty option)  
Email: warranty@oliveri.com.au

**New Zealand**  
Ph: 0800 440 606 (select Service & Warranty option)  
Email: warranty@oliveri.co.nz

If a warranty service call finds that the product does not have a genuine manufacturing fault, our Warranty Service Agent reserves the right to pass on any call-out fee to the householder. If we require you to return the Product, you must pay the expenses for such return.

WARRANTY CONDITIONS

We will (at our cost) either repair or replace (at our option) the Product at an equivalent value of the product purchased if it is discovered that the Product contains a material defect which arose during manufacture. We will pay the expense for shipment of the repaired or replaced Product to you. The warranty set out in the Warranty Statement above (other than sections 1(a)) is subject to the following conditions, and accordingly will not apply if:

(a) The Product was not new as at the date of purchase or proof of purchase details (such as invoice, receipt or transaction record) are not provided.

- (b) There is a failure to follow installation instructions, evidence cannot be provided that the Product was installed by a licensed plumber or the Product is used other than in accordance with product specifications. This includes operating conditions specified for temperature and pressure.
- (c) Repair work is performed on the relevant Product by a person other than us, our authorised service agents or any plumber who has not received authorisation from us prior to proceeding with the work.
- (d) Applicable statutes or regulations relating to public health are not observed and the Product must not have been damaged by misuse, accident or neglect.
- (e) Standards or regulations governing sewerage, plumbing, water supply and gas applicable to the location of the particular plumbing installation are not observed. This includes (without limitation) the Australian Standards (AS/NZ 3500.1 Plumbing and Drainage Part 1: Water services) which specify that the main water supply pressure to any new home, extension or renovation must be limited to 500kPa. The recommended continuous operating pressure for tapware is between 150-500kPa.
- (f) Harsh detergents or abrasive cleaners are used on any finishes of the Product.
- (g) The damage is edge chipping, surface damage caused by wear and tear, cracking or discolouration due to the Product being subjected to high heat or damage caused by improper use.
- (h) The Product must not contain excessive debris (in-line filters must be installed).
- (i) The Product has discolouration, natural pitting, corrosion or rusting from 'hard' water and/or other environmental factors.
- (j) Adequate access to products, fittings and fixtures to undertake extended warranty repairs is required. We will not be responsible for any consequential damage or costs where adequate access to product fittings and fixtures is not accessible.
- (k) Hairline cracking appears around cut-outs during or after installation of the Product.
- (l) The Product has been moved from original installations.


Installation Guide

Naples

Freestanding Bath With Overflow

NA1500-OF / NA1700-OF

- 10 year warranty (refer Oliveri website)
- Manufactured to Australian Standards
- Adjustable self-supporting feet
- Integrated overflow and pop-up waste included.



Manufactured from premium sanitary grade acrylic, Oliveri's freestanding baths are easy to install, with self-supporting, adjustable feet and can be freely located anywhere in your bathroom.

This manual is designed to provide the required installation steps and care advice, for a long-lasting product installation. Please follow these instructions carefully.

Proper use and care of your bath will ensure its ongoing high performance. Please consult the Care and Maintenance section of this guide for advice on regular cleaning and product care.



THIS BATH MUST BE INSTALLED BY A QUALIFIED TRADESPERSON IN ACCORDANCE WITH LOCAL REGULATIONS

Installer - Please read and follow these Installation Instructions.

STOP AND READ CAREFULLY



PRE-INSTALLATION CHECKS

- **Inspect the acrylic surface of the bath for damage. Damage found after installation is not covered by the manufacturer's warranty conditions. ANY CLAIMS FOR DAMAGE WILL NOT BE ACCEPTED AFTER INSTALLATION.**
- **Protect your bath before and during installation. Scratches, cracks or other surface damage sustained during or after the installation are NOT COVERED BY WARRANTY.**

Oliveri Solutions Pty Ltd ABN 12 007 551 886 For more information or any questions about this warranty, contact us or visit our website.

**Australia**  
51 Naweena Rd, Regency Park SA 5010  
P: 08 8 348 6444  
E: sales@oliveri.com.au  
oliveri.com.au

**New Zealand**  
PO Box 4641 Christchurch 8140  
P: 0800 440 606  
E: sales@oliveri.co.nz  
oliveri.co.nz

Any advice, recommendation, information, assistance or service provided by Oliveri Solutions in relation to goods manufactured by it or their use and installation, is given in good faith and is believed by Oliveri Solutions to be appropriate and reliable. However, any advice, recommendation, information, assistance or service is provided by Oliveri Solutions without responsibility or liability.

## CAUTION

**Risk of personal injury. Freestanding baths are heavy. Get help when lifting or moving. Be sure to use proper tools and always wear personal safety devices for your protection.**

### IMPORTANT

This bath is supplied with an integrated overflow system and pop-up waste pre-installed. However, the plumbing connection from bath overflow outlet to floor drain is not included.

1. Unpack the bath and check for any transit damage. **Do not install the bath if it is damaged.**
2. Position the bath in the desired location where it will be installed in the bathroom.
3. Check that the floor drain plumbing is suitably located for connection to the bath when in the desired location and that the location of the bath does not interfere with other bathroom fixtures.
4. Turn the height-adjustable feet to raise or lower the bath until the bath base is level and 3 - 5 mm above the finished floor surface.

### IMPORTANT

Installing the bath shell directly onto the bath floor will place pressure on the outside wall of the bath and can crack the bath.

**Ensure there is a gap of 3 - 5 mm between the bath shell and the floor.**

Installing the bath level is important to make sure all the water drains effectively to the waste outlet.

5. Raise the bath off the floor by propping it up onto timber blocks positioned at either end of the bath.
6. Connect the pre-installed bath overflow waste outlet to the floor drain outlet. We recommend using a flexible hose connector (not included). Please adhere to the manufacturer's instructions and all relevant sections of the plumbing standard AS/NZ 3500. Ensure the flexible connector is cut to the correct length for easier installation and to prevent drainage issues.
7. Carefully remove the timber blocks and use a spirit level to re-check that the bath is level with the floor and 3 - 5 mm above the surface. Adjust feet as necessary.
8. Before finishing the installation and securing the bath in position, water test for leaks and proper drainage.

### IMPORTANT



**Fill the bath with water and check that the water flows easily to the waste outlet.**

NOTE: A small amount of water may pool due to surface tension.


9. Carefully tilt the bath backward and apply a neutral-cure silicone adhesive to each of the bath feet. Lower the bath back into its final position.
10. Apply a thick bead of neutral-cure silicon sealant around the bath base and the finished floor ensuring that a watertight seal is formed. Allow sealant to set for 24 hours before using the bath.

## Technical Data

### NA1500-OF



This Oliveri bath is manufactured to Australian Standard AS 1172.5:2019



All dimensions in mm. Manufacturing tolerances apply:  $\pm 10$  mm

### NA1700-OF

